BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41620

APPROVED SCHEDULE - B

o.EE/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020

Name of Work:Patching pot holes in various roads of Bhadrappa badavane and surrounding areas in ward no. 8 kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SRIKANTH K S (AAKAR CONSTRUCTION)	
				In Figures	In Words
1	1043.38	KSRRB 300-45. Scarifying stone metal crust 50 to 100 mmthick with pick azxes along with premix carpet / surface dressing and stacking of old serviceable materials by manual means including cost of all labour charges complete as per specification. (Page No. 146, Item No. 19.51, PWD SR 2018-19)	Sqm	78.1	Rupees Seventy Eight and Ten Paise Only
2	208.68	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per MORTH specification No. 406, Page No. 155 / Item No. 20.18 / PWD SR 2018-19	Cum	1843.0	Rupees One Thousand Eight Hundred Forty Three Only
3	1043.38	KSRRB 3000: Filling Pot-holes and patch repairs with bituminous concrete, 40 mm, KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 back filling the pot hole with bituminous material as per clause 500.4 compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications, MORTH specification No. 3004.2, P. No. 259 / Item No. 35.5 PWD SR 2018-19	Sqm	336.0	Rupees Three Hundred Thirty Six Only

Signature of the Contractor

Executive Engineer 13/08
Byarayanapura Division
BBMP, Bangalore - 92
13/08